

Current Status of ATLAS Endcap Muon Trigger System

Takuya SUGIMOTO
Nagoya University



On behalf of ATLAS Japan TGC Group

Contents


1. Introduction
2. Assembly and installation of TGC
3. Readout test at assembly site
4. Full Big Wheel Test Plan
5. Summary

■ ATLAS Detector

■ General purpose detector for LHC

- Length: 44m
- Diameter: 25m
- Weight: 7000t

■ Data taking will be started from September 07.



TGC provides

- Bunch ID

- muon hit position

- Pt of muon


- EC toroidal magnet

- 2 station coinc.

 - low Pt trigger ($>6\text{GeV}$)

- 3 station coinc.

 - high Pt trigger ($>20\text{GeV}$)



Thin Gap Chamber

5/23

Performance requirements

- ① Detection efficiency > 99% → Trigger
- ② Signal response time ~ 25nsec → BC ID
- ③ Stable operation for more than 10 years under high rate environment ($\sim \text{kHz}/\text{cm}^2$)
- ④ Radiation Tolerance ($\sim 0.6\text{C}/\text{cm}$)


Structure of TGC

Similar to MWPC

- Wire : $50\mu\text{m}$ gold-plated W
- Anode-Cathode Gap : 1.4mm
- Wire-Wire Gap : 1.8mm
- 2-dimensional readout (wire, strip)
- Cathode plane: carbon ($\sim \text{M}\Omega/\text{cm}^2$)
- Trapezoidal shape ($\sim 2\text{m}^2$)

Operation condition

- Gas : $\text{CO}_2 + \text{n-Pentane}$ (55:45)
- High Voltage : +3.0kV
- Operation Mode : Limited Proportional
- Gas Gain : $\sim 10^6$



■ Mass production of chambers

■ Total:3,600 chambers (11 types)

- Produced in Japan, Israel and China.
- Total channel:~ 320,000 channels
- Covered area:~ 2,700m²

■ Japanese contribution

- Total : 3 types, 1,224 chambers (inc. spare)
- Period : Apr. 2001~Feb. 2005 (48 months)
- Site : KEK (Fuji experimental hall)



Carbon painting



Wire winding



Close chamber

■ Chamber performance test in Japan

■ Test Stand at Kobe University

- Period: May 2001 ~ July 2005 (40 months)

■ Check following items using cosmic ray

- Detection efficiency (5mm x 5mm)
- Timing distribution

■ Result for Japanese chambers

- **12 chambers** with locally inefficient region.

– Not transported to CERN

■ Transportation from Kobe to CERN by ship

- All good chambers were already transport to CERN





Diagram of TGC Electronics

TGC1 TGC2 TGC3

On TGC chambers

Big Wheel edge

Counting Room



TTC: Timing Trigger Control

DCS: Detector Control System

TGC Electronics Modules made in Japan

TGC1 TGC2 TGC3

On TGC chambers

Big Wheel edge

HSC(VME)
(Big Wheel edge)

C

V

T


ASD




ASD



ASD



ASD card



SSW Board

BCID

Triplet


DCS-P

Service PP

TTC signal fanout
to PS-Boards


CA

TTC



PP

SLB



H-Pt

board

HSC Board

PS Board

Trigger Control


DCS: Detector Control System

Assembly and Installation of TGC

Assembly unit


11/23

- TGC consists of three wheels
 - We call this “Big Wheels” (BW)
 - Triplet (TGC1)
 - middle doublet (TGC2)
 - pivot doublet (TGC3)
 - located at each end-cap (A-side and B-side)
- Each BW consists of 12 sectors
 - TGC1: 18 triplet modules/sector
 - TGC2,3: 22 doublet modules/sector→ 1488 modules in total.



Two Working Areas @ CERN

SITE DE MEYRIN



Storage of 1/12 sector



ATLAS pit

Sector Assembly Procedure



13/23

1. Chamber preparation before installation

- Check gas tightness of chamber

2. Assembly in horizontal position

- Assembly of Al frame for sector
- Arrangement of cables (signal and LV/HV)
- Arrangement of gas pipe



Sector Assembly Procedure (cont)

14/23


3. Assembly in vertical position

- Chamber installation

4. Install on-detector electronics

5. Test of sector

- Check cabling and electronics health
 - Send test pulse to ASD card
- Apply high voltage to chambers with CO₂ gas flow
- Test with RI source & cosmic ray



SSW, HSC boards



PS Boards

■ We have checked cabling before installation

- 12 x TGC1 sectors and 12 x TGC2 ones were tested.

- TGC3 is tested now.

- Have found some problems and fixed them.

- insufficient connection

- cable swapping

- broken cables

- electronics failure

- dead channels on chamber


- In TGC1 test, all electronics channels (~30k channels) were checked.

- Only five channels on chambers were found to be dead (0.017%).

■ Delay scan method

- To confirm timing adjustment functionality

- Take data with changing test pulse delay values with accuracy of sub-nano second




Progress of sector assembly

16/23

- Assembly work is performed in parallel on 2 sites at assembly site.
 - We have already tested 12 x M1-C sectors and 12 x M2-C ones.
 - Now we are assembling M3-C
 - 4 sectors were already installed.
 - M1-A will be assembled from this November using 3rd site.

1 sector/week



Installation to ATLAS pit

17/23



Transport to the pit



Lower down to the pit



Built up to a BW

Schedule

	station	Assembly	Installation
C-side	TGC1	Done	Done
	TGC2	Done	Jan.07 -
	TGC3	In progress	Feb.07 -
A-side		Nov.06 -	Jan.07 -

- Assembly and installation of C-side TGC is in progress
 - 1st BW has been fully installed in the pit
 - 2nd BW is ready for installation
 - Stocked in assembly site
- Services to be performed in the pit
 - Check distortion of BW
 - Check electronics and DCS
 - Gas, LV/HV and optical fiber
- Installation of A-side TGC will be started from Jan. 07

Future test programs foreseen in the pit

■ Timing adjustment

- TGC must make level1 trigger decision at each 40MHz bunch.

■ Strategy

1. Before beam collision



- Timing adjustment is synchronized to 40MHz clock

2. After beam collision

- Adjust phase between bunch crossing timing and L1A signal.

■ Pre-run

- Cosmic run
- Single beam halo run
 - provide trigger signal
 - need special configuration (1 station coincidence)



■ Thin Gap Chamber

- Used as ATLAS Level1 endcap muon trigger chamber
- Almost chambers were produced and tested their performance.

■ Assembly and Installation

- TGC modules are assembled to 1/12 sectors.
 - TGC1 and TGC2 for side-C have been assembled.
 - TGC3 are assembled now.
 - TGC1 for side-A will start to be assembled from this November.
- The first Big Wheel station (TGC1) was installed on this September.
 - TGC2 will be installed in Jan. 07.
- Sector Test
 - To check on-detector electronics and cabling.
 - TGC1 and TGC2 for side-C have been checked.
- We continue sector tests for remaining sectors in cooperation with sector assembly.

■ Future Plan

- We will start full big wheels test from Mar.07
 - Timing adjustment
 - Cosmic & beam halo run

	station	Assembly	Installation
C-side	TGC1	Done	Done
	TGC2	Done	Jan.07 -
	TGC3	In progress	Feb.07 -
A-side		Nov.06 -	Jan.07 -



Backup slide

Result for RI source & cosmic ray test

23/23





RI source test



- 1MBq ^{60}Co was used.
- CO_2 flow, 2.8kV?
- Only very few hot channel was found.



Cosmic ray test


- Random trigger
 - 100kHz clock







Procedure

1. Set test pulse delays properly.
2. Confirm necessary signal delay values by checking test pulse data timing adjustment is synchronized to 40MHz clock





Bunch crossing



40MHz TTC clock

■ Procedure

1. Take data with changing TTC clock skew.
2. Confirm signal delays with synchronized to beam collision by checking data.

